

Hg System Assembly and Testing Status

V.B. Graves


P.T. Spampinato

MERIT VRVS Meeting

Dec 6, 2006



Primary Containment Completed

- Issues with piping resolved, final fit-up completed
- Optical diagnostic system installed and operational




SS Water Test Nozzles

- **Nozzle A** – diameter reduction after bend, 2.5° nozzle angle
- **Nozzle B** – reduction before bend, 2.5° nozzle angle
- **Nozzle C** – test nozzle with reduction after bend, straight nozzle tip




Results


- **Nozzle B spray worse than Nozzle A**
 - Neither jet was acceptable
- **Definite increase in jet diameter at higher velocities**
- **Nozzle C gave best results**
- **Water droplets on windows was a problem**



Nozzle A, 20m/s




Nozzle B, 20m/s



Nozzle C, 20m/s


Nozzle Issues

- **Flow path is a three-piece weldment**
 - Inlet tube
 - Nozzle flange
 - Short angled nozzle tip
- **Smooth path requires constant ID**
- **Investigation revealed SS nozzles had step in flow path (flange thru hole smaller than tube IDs)**




Modified Nozzle A Tested

- Nozzle A was manually modified using drill bits to provide nearly constant ID from flange to tip
- Tests showed definite improvement



Nozzle A As Received, 20m/s



Nozzle A After Mods, 20m/s



Proposed Path Forward

- **Proceed with fabrication of Ti nozzle A as designed**
- **Ensure constant ID of flow path prior to weldment**
- **Perform final reaming of nozzle tip**
- **Leave extra nozzle tip length for pressure testing**



Readiness Review Conducted

- **Internal ORNL review held to determine if necessary steps are in place for mercury operations**
- **No issues noted as long as safety equipment is in place and operating procedures are followed**
- **Have ordered replacement pond liner since original sent to MIT**
- **Awaiting Hg filter housings**



Current Status / Next Steps

- **Complete secondary containment**
 - Check for pressure leaks
 - Install Hg vapor filters
- **Remove nozzle, clean inside of viewports, reinstall nozzle**
- **Drain water and replace with Hg**
 - Perform Hg tests with nozzle A
- **Await Ti nozzle A or proceed to MIT?**
 - Equipment crating is being fabricated